

TRENCHING ACROSS ROAD REQUIREMENTS

If, in installing utilities, trenching across The Meadows roads is necessary, the following requirements must be met:

1. Asphalt to be cut 6" each side of trench width.
2. A certified compact test will be required.
 - Initial backfill layers – 8" lifts - 90% compaction required
 - Top 12" – Class II asphalt base - 95% compaction required
3. Tack coat to be applied to cut surfaces.
4. Asphalt section shall match existing asphalt depth.
5. Asphalt applied shall meet California Department of Transportation specifications – ½" hot mix asphalt.
6. Asphalt to be crowned 1/2" to allow for settling.
7. Asphalt to be mechanically compacted, not wheel rolled.
8. If trench is to be left unpaved for more than one week, it must be patched temporarily with cold-mix asphalt.
9. Finished paving must be completed within one month of trenching starting date.
10. If settling, potholes, etc. occurs, the owner will be responsible for repair.